Checklists



for surveying and assessing industrial plant handling materials and substances which are hazardous to water

Federal Environmental Agency Federal Republic of Germany

No. 6 Split-Flows Wastewater

Recommendations of the International River Basin commission for splitflow wastewater

- 1 Accidentally contaminated split-flow wastewater must be identified early with such measures like monitoring. The monitoring must be done in conjunction with the recommended checking measures.
- 2 If possible, accidentally contaminated split-flow wastewater should be contained at the source of discharge and if necessary the sewer for their collection should only be for this purpose.
- 3 Accidentally contaminated split-flow wastewater should not be mixed with other wastewater.
- 4 Steps must be taken to ensure that substances which constitute a fire or explosion risk can not find their way into the wastewater system even when the system is protected against such dangers.
- 5 Suitable containment facilities of adequate size must be provided for accidentally contaminated split-flow wastewater. Such facilities must be tight and resistant to the spill for the expected duration of exposure.
- 6 Measures (e.g. holding ponds, re-circulation of wastewater) must be provided for preventing contamination of waters in the event of an accidental reduction in the purification capacity of the treatment plant.
- 7 The wastewater systems must be tight and resistant to the expected physical, chemical, thermal and biological stress.
- 8 For possible accidental contamination of split-flow wastewater, the internal and external countermeasures, the information and notification duties must be stipulated in the hazard control planning.
- 9 Ensure the safe disposal of accidentally contaminated split-flow wastewater.
- 10 The effectiveness of the technical and organisational measures taken must be guaranteed by regularly conducted checks.




Checklist for monitoring the implementation of the recommendations

0. Introduction

Split-flow wastewater are continuous and discontinuous industrial wastewater (like wastewater from production plants, auxiliary facilities and laboratories) as well as cooling and rainwater As a matter of principle suitable technology (e.g. utilization of air cooling systems, water free vacuum systems etc.), environmentally friendly production processes and alternative production process should be considered to avoid wastewater when drawing up concept for wastewater systems. Open water cooling system should be avoided. If it is not possible to avoid generating wastewater or contaminating them, then a wastewater treating system is necessary to treat the wastewater, to purify it in such a way that it can be disposed for example, to the surface water through the sewage system.

Example of a wastewater treatment plant:



Low-density-liquid separating plant - LFA - for oily wastewater

- 1 In and Outlet
- 3 Shaft structure
- 5 Pipe connections
- 7 Inlet set
- 9 Swimmer
- 11 super elevation

- 2 connection of container wall/cover plate
- 4 baffle plate
- 6 connection of cover plate/Shaft structure
- 8 automatic ends
- 10 ree pipes for eventual installation of alarm device



Ch	ecklist no. 6:	Split-Flow Wa	stewater			Page 4 of 15	
1.	1. Monitoring contaminated split-flow wastewater						
1.1	1.1 Which split-flow wastewater is available?						
-	Process wastewa	ater					
	Present		Not applicable		Not kno	wn	
-	Is the wastewate	r from the drainir	ng surfaces and co	ntainment facility	of a pro	oduction plants?	
	Yes		Not applicable		Not kno	wn	
-	Is the wastewate	r from the contain	nment facility of sto	orage unit and po	ort of tra	nsshipment?	
	Yes		Not applicable		Not kno	wn	
-	Other contamina	ted wastewater					
	Yes		Not applicable		Not kno	wn	
1.2	Can leakages fr	om accidental r	eleases lead to c	ontamination of	wastev	vater?	
	Yes		No		Not app	licable	
1.3	Can these accio measures?	dental contamina	ations be detecte	d in time with s	uitable	monitoring	
	Yes		No		Not app	licable	
	Action		No action				
1.4		e measures be u face water after	used to prevent n the pollution?	egative effects	of the re	elease on	
	Yes		No		Not app	licable	
	Action		No action				



1.5 Are the monitoring measures timed with the necessary preventive measures?

🗖 Yes	🗖 No	Not applicable
Action	No action	

Remarks:

Examples of actions:

Short-term measures:

- Regular visual checks on the plant, particularly those containment facilities for the storage and transshipment units which are connected to the wastewater system without shut-off valves.
- Sampling of wastewater flows from production facilities, or periodic sampling of the wastewater before being discharged into surface waters.

Medium-term measures:

 Containment facilities for the storage and transshipment facilities should be separated from the wastewater system with shut-off valves. Uncovered secondary containment belonging to the storage facilities should be drained by the operating personnel whenever necessary and if necessary be sent to a wastewater treatment plant.

Long-term measures:

- Split-flow wastewater from production plants which could be accidentally contaminated are to be continuously monitored by automatic sensors or systems. In case of an alarm, the acoustic and optical alarm signals should be transmitted to a central monitoring room.
- Monitoring the quality of the wastewater before discharging it to the surface water with automatic analysing equipment which automatically triggers off an alarm or emergency measures such as automatic activation of a shut-off device to interrupt the discharge of wastewater to the surface water.
- Providing retaining capacity to contain contaminated wastewater.
- Liquid from uncovered secondary containments should only be discharged indirectly to the wastewater system after being analysed with the aid of a pump.

Determination of the real risk					
Is the sub-point of the recommendation implemented?					
Yes □ RC=1	Partially D RC=5	No □ RC=10			



Checklist no. 6:	Page 6 of 15				
2. Containment at	the point of discharge				
2.1 Can accidentally contaminated split-flow wastewater possibly be contained at the point of discharge?					
🗖 Yes	🗖 No	Not applicable			
2.2 Can the sewer for split-flow wastewater be separated from other sewers with a shut- off device if necessary?					
🗖 Yes	🗖 No	Not applicable			
C Action	No action				

Remarks:

Examples of actions:

Short-term measures:

• Drainage facility of containment facilities (storage and transshipment) without shut-off devices should be designed with a simple shutting gadget to drain liquid when necessary. The shut-off valve of the drainage system should be closed during the process of transshipment

Medium-term measures:

• Secondary containments and retention facilities for outdoor storages and transshipment facilities being drained through the wastewater system should be equipped with shut-off devices so that any water-polluting substances released can be contained.

Long-term measures:

- Equip facilities for split-flow wastewater of a production plant with shut-off which can be operated with an automatic system (see point 1).
- Build wastewater treatment plant to purify or treat wastewater.

Determination of the real risk					
Is the sub-point of the recommendation implemented?					
Yes ⊐ RC=1	Partially D RC=5	No □ RC=10			



Checklist no. 6: Split-Flow Wastewater					
3. Preventing contaminated wastewater from being mixed with other wastewater					
3.1 Is there the possibility of accidentally contaminated wastewater being mixed with other wastewater?					
🗖 No	Not applicable				
	ed wastewater with other wastewater be ures or at least limit the risk?				
🗖 No	Not applicable				
No action					
Remarks:					
	ed wastewater from being ty of accidentally contami				

Examples of actions:

Short-term measures:

• Taking steps to temporarily interrupt or stop the discharge of wastewater to the sewer in case of accident or breakdown.

Medium-term measures:

- Installation of shut-off devices in case of accidental releases.
- Prevention of accidentally contaminated wastewater from being mixed with other wastewater by installing:
 - fast-closing shut-off devices,
 - Separate sewer for contaminated wastewater.

Determination of the real risk

Is the sub-point of the recommendation implemented?

Yes	Partially	No
RC=1	RC=5	RC=10

4. Fire and explosion hazard

□ relevant

not relevant



Federal Environmental Agency Federal Republic of Germany

4.1 Substances with fire and explosion risks must be prevented from entering the drainage system. Are the preventive measures sufficient? (See also <u>Checklist No 1</u> <u>Substances</u>)

	Yes		No		Not applicable
4.2	Is the drainage system des	signe	ed to handle substances with	n fire	and explosion risks?
	Yes		No		Not applicable
	Action		No action		

Remarks:

Examples of actions:

Short-term measures:

- Replace unsuitable components of the drainage system.
- Take measures to prevent these dangerous substances from entering the drainage system.

Medium-term measures:

• Prevent these dangerous substances from entering the drainage system by containing them at the point of release (close the shut-off valve of the drainage system).

Long-term measures:

٠

- Construct the sewer in question according to the appropriate standards:
 - Construct wastewater drainage systems pipes with non-flammable and corrosionresistant material,
 - construct wastewater drainage systems pipes and the sewer itself to resist pressure surge.
- Ensure there are no sources of ignition in the drainage systems and its piping.
- Avoid the mixture of substances which can lead to explosive reactions.

Determination of the real risk Is the sub-point of the recommendation implemented? Yes No RC=1 RC=10



Checklist no. 6:		Split-Flow Wastewater	Page 9 of 15	of 15
5. Containing split-flow was		flow wastewater and tightness of containm	ent systems	
5.1		y dimensioned containment facilities for accerted evaluation and the second states and t	cidentally contaminated	

D Not applicable

_		_	-
	Action		No action

5.2 were the available retention facilities leak-proof for the period they are in operation?

Yes	No	Not applicable
Action	No action	

Remarks:

☐ Yes

Examples of actions:

Short-term measures:

- Construct temporary containments.
- Regular assessment of the tightness at short intervals, at least through visual inspections.
- Repair detected damages to the sealing.

Medium-term measures:

- Construction of containment. Use the highest wastewater flow-rate to design the containment systems.
- Specify the period for which the seals of a retention basin must be tight and resistant to accidentally contaminated wastewater.
- Specify measures for the treatment or disposal of accidentally contaminated wastewater.

Long-term measures:

• Installation of an automatic level monitoring system to monitor fluid levels in the containment basin.



Determination of the real risk							
Is the sub-point of the recommendation implemented?							
Yes □ RC=1	Partially D RC=50	No □ RC=100					

6. Operation and function of treatment plants

6.1 Can accidentally contaminated split-flow wastewater flow to an in-house plant or to other public treatment plants?

L Yes	D No	Not applicable
-	ort of an in-house or public treatr flow wastewaters are treated the	-
🗖 Yes	🗖 No	Not applicable
	ace waters by accidentally conta stems or wastewater recycling sy	
🗇 Yes	🗖 No	Not applicable
C Action	No action	
Remarks:		

Examples of actions:

Short-term measures:

- Regular and frequent checking of the treatment plant's efficiency by internal quality control of the wastewater before being discharged into surface waters or indirectly discharged through the public sewer system.
- Specify measures in conjunction with the operator of the treatment plant before any indirect discharge into the public sewers.



Federal Environmental Agency Federal Republic of Germany

Medium-term measures:

- Construction of containment facilities which are sufficiently tight and have enough containment capacity for this purpose.
- Equip the facilities with shut-off device to stop the discharge of wastewater into public wastewater facilities or surface waters.

Long-term measures:

- Installation of automatic and continuous monitoring devices so that the discharge of accidentally contaminated wastewater resulting from accidents can be prevented at all time.
- Improvement of production technology and technical systems to prevent the occurrence of breakdowns which could lead to wastewater contamination.

Determination of the real risk						
Is the sub-point of the recommendation implemented?						
Yes ⊡ RC=1	Partially □ RC=5	No □ RC=10				

7. Tightness and durability of the wastewater systems

7.1 Are the wastewater systems tight and resistant to the physical, chemical, thermal and biological stresses to be expected?

🗖 Yes	🗖 No	Not applicable
C Action	No action	

Remarks:

Examples of actions:

Short-term measures:

- Inspection of the visible parts of the wastewater facilities (where possible) in regard to their internal and external condition.
- Repair or replacement of damaged parts.
- Inspection of the facility's documentation in regard to the resistance of the piping to the present composition of the wastewater.



Checklist no. 6: Sp	plit-Flow Wastewater
---------------------	----------------------

Medium-term measures:

 Tightness test of the wastewater system. The testing is to be carried out section by section and should be documented.

Long-term measures:

- Replacement of unsuitable parts.
- Closing of unsuitable facilities.

Determination of the real risk							
Is the sub-point of the recommendation implemented?							
Yes □ RC=1	Partially ☐ RC=5	No □ RC=10					

8. Preventive measures and task of reporting

8.1 Are internal and external preventive measures specified for contaminated split-flow wastewater in the danger prevention plan?

	Yes				No]	Not	app	olica	able	
~ ~						 								~

8.2 Are the tasks of information and notification specified for contaminated split-flow wastewater in the danger prevention plan?

🗖 Yes	🗖 No	Not applicable
C Action	No action	

Remarks:

Examples of actions: <u>Short-term measures:</u> Put the most important preventive measures to be taken in the case of an accident or breakdown in writing. Existing danger prevention plan documents should be updated. Determine and specify necessary measures in conjunction with external experts e.g. the fire brigade. Check the extent of availability of adequate in-house technical aid for danger prevention.



Federal Environmental Agency Federal Republic of Germany

Checklist no.	6: S	plit-Flow	Wastewater

• Specify the necessary information to be reported and the content of such report in co-operation with the local authority responsible for such cases.

Medium-term measures:

- Development of internal alarm/danger prevention plans.
- Danger prevention training for the staff involved.

Determination of the real risk

Is the sub-point of the recommendation implemented?

Yes	Partially	No
RC=1	RC=5	RC=10

9. Disposal of accidentally contaminated wastewater from accidental discharge

9.1 Is the safe treatment/disposal of accidentally contaminated wastewate guaranteed?

🗖 Yes	🗖 No	Not applicable
Action	No action	

Remarks:

Examples of actions:

Short-term measures:

- Assess possible methods of disposal.
- Specification of the necessary disposal measures.
- Name a member of the staff to take the responsibility for the disposal.

Medium-term measures / Long-term measures:

- Acquisition of additional equipment for the disposal of accidentally contaminated wastewater resulting from accident, such as:
 - Containers (for transport),
 - Mobile pumps,
 - Flexible tubes/hoses for pumping and transporting the wastewater
 - Analytical equipment.




Federal Environmental Agency Federal Republic of Germany

Determination of th	ne real risk		
Is the sub-point of th	e recommendation impleme	ented?	
	Yes □ RC=1	No □ RC=10	

10. Regular checks

10.1 Are regular checks to prove the sufficiency of the organisational and technical measures taken regularly carried out?



Remarks:

Examples of actions: Short-term measures: Responsibilities and duties for carrying out inspections should be assigned to production plant • staff. Training of production plant staff on how to carry out inspections. . The scope of inspections should be specified by the member of staff responsible for the • inspection The inspections should guarantee the following: • - is the monitoring of split-flow wastewater efficient. - Examination of the visible parts of the wastewater system (as far as possible) in regard to leakage, excessive corrosion or other defects. - is the tightness of the wastewater system verified or has sufficient measures been taken to prove the tightness of the wastewater system. Medium-term measures / Long-term measures: Training of plant staff to monitor the wastewater system. • • Involvement of independent/external expert in the regular inspection of the wastewater system.



Determination of the real risk			
Is the sub-point of the recommendation implemented?			
Yes □ RC=1	Partially □ RC=5	No □ RC=10	

Summery of the Checklist

Sub-point of the Recommendation	Possible Risk category	Risk categories
1	1 / 5 / 10	
2	1 / 5 / 10	
3	1 / 5 / 10	
4	1 / 10	
5	1 / 50 / 100	
6	1 / 5 / 10	
7	1 / 50 / 100	
8	1 / 5 / 10	
9	1 / 10	
10	1 / 10	

Average Risk of the Checklist (ARC)

